



March 8, 2017

Ms. Diane Williams
 GLENDALE CIVIC CENTER
 5750 West Glenn Drive
 Glendale, AZ 85301
 (623)930-4312
 FAX: (623)930-4319

Project: CROWNE BALLROOM WALL "C", "D" & "E"
 Subject: Modernfold Operable Wall #14 Track & Trolley System

Per your request, NORCON Industries, Inc., would like to furnish our proposal regarding the above reference project as follows:

ACOUSTI-SEAL 931 – as manufactured by Modernfold, Inc., of Dyersville, Iowa as distributed by NORCON of Guadalupe, AZ.

WALL "C" RH RADIUS

- Provide labor, equipment & materials to convert existing 860 Track into #14 Track for an opening with dimension as follows: 43'-0" x 16'-0" "Wall "C"
- Heavy Duty Bracket mounted #14 Right Hand Radius parallel stack track design.
- Provide all new special #14 Trolleys with milled pendant bolts to adapt to existing panels onsite.
- **Special Note:** Glendale Civic Center to open up the finished ceiling 12" on both sides of existing track in order to gain access to track brackets for removal of existing 860 Track for installation of new #14 track system. Once #14 tracks are installed Glendale Civic Center shall be responsible for closing up soffit back to new track installation.
- Provide 86' / 43' per each side of #14 drop soffit trim for new finish at ceiling.
- Adjust all panels for proper alignment; lock off all trolley blocks.
- Provide scissor lifts for track & trolley installation.
- Based upon Mohave Contract #16G-NPAR-0916

DELIVERED & INSTALLED AS INDICATED FOR THE SUM OF \$21,369.78

5412 E. CALLE CERRITOS	GUADALUPE, AZ 85283	PHONE: (480) 839-2324	FAX: (480) 839-2281
2840 W. RUTHRAUFF RD., STE. 140P	TUCSON, AZ 85705	PHONE: (520) 325-5752	FAX: (520) 325-5753
1905 VILLA PARK LANE	HOLLADAY, UT 84121	PHONE: (801) 803-8766	FAX: (801) 384-1240
Send all Remittances & Secure Documents to: Norcon Industries, Inc. • P.O. Box 61988 • Phoenix, AZ 85082-1988			

WALL "D" " RH RADIUS

- Provide labor, equipment & materials to convert existing 860 Track into #14 Track for an opening with dimension as follows: 52'-9" x 16'-0" "Wall "D"
- Heavy Duty Bracket mounted #14 Right Hand Radius parallel stack track design.
- Provide all new special #14 Trolleys with milled pendant bolts to adapt to existing panels onsite.
- **Special Note:** Glendale Civic Center to open up the finished ceiling 12" on both sides of existing track in order to gain access to track brackets for removal of existing 860 Track for installation of new #14 track system. Once #14 tracks are installed Glendale Civic Center shall be responsible for closing up soffit back to new track installation.
- Provide 106' / 53' per each side of #14 drop soffit trim for new finish at ceiling.
- Adjust all panels for proper alignment; lock off all trolley blocks.
- Provide scissor lifts for track & trolley installation.
- Based upon Mohave Contract #16G-NPAR-0916

DELIVERED & INSTALLED AS INDICATED FOR THE SUM OF \$24,062.48

WALL "E" " LH RADIUS

- Provide labor, equipment & materials to convert existing 860 Track into #14 Track for an opening with dimension as follows: 52'-9" x 16'-0" "Wall "E"
- Heavy Duty Bracket mounted #14 Left Hand Radius parallel stack track design.
- Provide all new special #14 Trolleys with milled pendant bolts to adapt to existing panels onsite.
- **Special Note:** Glendale Civic Center to open up the finished ceiling 12" on both sides of existing track in order to gain access to track brackets for removal of existing 860 Track for installation of new #14 track system. Once #14 tracks are installed Glendale Civic Center shall be responsible for closing up soffit back to new track installation.
- Provide 106' / 53' per each side of #14 drop soffit trim for new finish at ceiling.
- Adjust all panels for proper alignment; lock off all trolley blocks.
- Provide scissor lifts for track & trolley installation.
- Based upon Mohave Contract #16G-NPAR-0916

DELIVERED & INSTALLED AS INDICATED FOR THE SUM OF \$24,062.48

5412 E. CALLE CERRITOS	GUADALUPE, AZ 85283	PHONE: (480) 839-2324	FAX: (480) 839-2281
2840 W. RUTHRAUFF RD., STE. 140P	TUCSON, AZ 85705	PHONE: (520) 325-5752	FAX: (520) 325-5753
1905 VILLA PARK LANE	HOLLADAY, UT 84121	PHONE: (801) 803-8766	FAX: (801) 384-1240
Send all Remittances & Secure Documents to: Norcon Industries, Inc. • P.O. Box 61988 • Phoenix, AZ 85082-1988			

TYPICAL EXCLUSIONS FOR ALL THREE WALL LOCATIONS:

EXCLUSIONS:

Any & all quantities, sizes, products, options not listed above, blocking, bracing insulation, sound testing or related fees, upper structural support of any kind, sound baffling/insulation above finished ceiling, floor leveling, moving light fixtures, sensors, removal & relocation of HVAC ducts, fire sprinklers, electrical conduits, building power to final electrical connect at junction box, key switches, caulking, punching of holes for track brackets, protection during storage or after installation, storage/storage fees, delegated design submittal, coordination drawing, engineering drawings/stamps/testing, seismic test/reports and qualification certificates, FSC-accredited certification, forest certification, permits, any & all asbestos abatement of any kind and bonds.

Pricing is based upon acceptance within 60 days and installation of track & trolleys by end of year 2017. If there are any questions, please give us a call.

Respectfully,

NORCON INDUSTRIES, INC.



Peter Willman | Norcon Industries, Inc.

5412 E. Calle Cerritos, Guadalupe AZ 85283

Telephone: 602.320.9134 | Fax: 480.994.3938

Email: petew@norconindustries.net | Web: www.norconindustries.net

EOE/ AA/ EMPLOYER

NORCON INDUSTRIES, INC.

ARIZONA | COLORADO | IDAHO | NEW MEXICO | TEXAS | UTAH | WYOMING

5412 E. CALLE CERRITOS	GUADALUPE, AZ 85283	PHONE: (480) 839-2324	FAX: (480) 839-2281
2840 W. RUTHRAUFF RD., STE. 140P	TUCSON, AZ 85705	PHONE: (520) 325-5752	FAX: (520) 325-5753
1905 VILLA PARK LANE	HOLLADAY, UT 84121	PHONE: (801) 803-8766	FAX: (801) 384-1240
Send all Remittances & Secure Documents to: Norcon Industries, Inc. • P.O. Box 61988 • Phoenix, AZ 85082-1988			